

6DI30Z100

Darlington Three-Phase Bridge

Various

Isolated Case (Y/N)=Yes

Circuits Per Package=1

V(BR)CEO (V)=1.0k

V(BR)CBO (V)=1.0k

I(C) Abs. (A) Collector Current=30

h(FE) Min. Static Current Gain=100

@I(C) (A) (Test Condition)=30

@VCE (test)=5.0

t(r) Max. (s) Rise time=2.5u

t(f) Max. (s) Fall time.=2.0u

Package=Module-q